participate in any profit from such resale. The amount due by such defaulter on account of loss from resale shall be recovered from him as a revenue demand under section 79 of the Mysore Forest Regulation. In calculating such losses, the initial deposit forfeited to Government shall not be taken into account.

In cases of resales for default of payment of value where no bidders are forthcoming, it will be open to the District Forest Officer to fix such price as may appear to him to be reasonable and to proceed for the recovery from the defaulter of the balance, if any, after deducting the price so fixed from the original sale amount. A registered notice should be issued to the defaulter intimating the price fixed by the District Forest Officer, for the unsold wood and the amount still due from him which will be recovered as arrears of Land Revenue.

6 The deposits tendered by the unsuccessful bidders shall be returned immediately after the sales are concluded, those of successful bidders being lodged in the Savings Bank as security deposit.

7. The full value of all timber purchased shall be paid for within 30 days after the date of sale or within fifteen days after the date of the notice of confirmation of the sale, whichever is later. In case of purchases above Rs. 1,000 in value, the purchaser shall be permitted to pay up the balance in instalments of not less than Rs. 1,000, provided the full value is paid not later than the 15th June 1929. The moneys shall be paid into such treasury as the District Forest Officer may direct, within the time specified.

8. If the amount is not fully paid for by the purchaser before the dates fixed above, the initial deposit as well as the other moneys already paid in, shall be forfeited to Government and all or any portion of the timber not fully paid for shall be resold at the risk of the purchaser in the manner prescribed for default of payment of one-tenth value in clause 5 *supra*.

9. No timber lot shall be permitted to be removed by the purchaser unless it has been paid for in full, calculated at the rates at which the timber is knocked down to him at the time of sale, excluding the ten per cent deposit paid for the lot at the time of the sale; and no timber shall be removed from the depot unless a permit is obtained from the Forest Officer in charge of the Depot. The earnest money will not be adjusted towards the value of timber, until 90 per cent of the purchase money over and above the security deposit has been paid.

10. Timber purchased should be removed as early as possible, and in no case should it be allowed to remain longer than 90 days after the dates fixed in clause 7 *supra*. Timber not removed after purchase, will remain in the depot at the risk of the purchaser from the date of the confirmation of the sale.

11. If the timber is not removed within the time allowed, the same may, after ten days' notice to the purchaser, be sold in public auction and the proceeds will be given to the purchaser after defraying all the expenses in connection with the resale.

12. The deposit of Rs. 200 will remain as security for the due fulfilment of all and every one of the terms of sale, on the breach of any of which by the purchaser, the District Forest Officer shall be entitled to forfeit the deposit in whole or in part and in the event of such forfeiture, the sum so forfeited shall be immediately made good by the purchaser so long as the transaction is not finally closed. The security deposit or the balance thereof, if any, shall be returned to the purchaser after the full value of timber purchased has been paid for and the timber fully removed. Timber of defaulters will also be auctioned.

H. A. GOVINDA RAO,
District Forest Officer.

BHADRAVATI DIVISION.

Abstract Notification dated 18th March 1929.

The attention of the public is invited to detailed notification, dated 18th March 1929, regarding the sale of timber in Tarikere Depot in auction to be held on the 27th April 1929, published on pages 339 to 340, Part VI of the *Mysore Gazette*, dated 28th March 1929.

K. REVANNA,
District Forest Officer.

SANITARY AND TOWN PLANNING DIVISION.

Abstract Notification.

The attention of the public is invited to the detailed notification calling for sealed tenders for constructing the Engine House, etc., at Hunsur, published on pages 341 and 343 of Part VI of the *Mysore Gazette*, dated 28th March 1929. The last date for receiving tenders is 26th April 1929.

H. F. MARKER,
Executive Engineer.

No.	Items of work	Per	Rate	Quantity	Cost	Total
	Sluice—concld.		Rs.a.p.		Rs	Rs.
5	Burnt stone slabs 6" thick dressed ...	S.ft.		332		
6	Surki mortar plastering	Sqr.		6·52		
7	Providing plug and rod with locking arrangements.	L. S.		...		
8	Drilling holes in orifice slabs	L. S.		...		
9	Cutting approach and draft in hard soil ...	C.yds.		43		
10	Dismantling the existing sluice and removing debris and bailing water, etc.	L. S.		...		
	Total Sluice ...	...	...	...	...	
	Waste Weir.					
1	Earthwork	C.yds.		241		
2	Surki concrete	C.ft.		210		
3	Burnt brick in surki mortar	,,		532		
4	Burnt stone slabs new dressed	S ft.		736		
5	Surki mortar plastering	Sqr.		9·50		
6	New stone work	C.yds.		118		
7	Draft and approach clearing in soft rock ...	,,		812		
8	Removing rock holders in front of body wall ...	L. S.		...		
9	Providing jaggle joints	No.		30		
	Total Waste Weir ...	...	...	...	...	
	Total bund sluice and waste weir contingencies at 5 per cent.	...	...	...	...	
	Grand Total Rs. ...	...	...	...	...	

Notice dated 31st March 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 22nd April 1929, for Restoring Kaderanahalli Dodkere Tank, Registered No. 702, Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Kadarenahalli Dodkere, Bowringpet Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor, will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be ferfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate of the cost of Restoring Kaderenahalli Doddakere, Bowringpet Taluk.

Items of work	Per	Quantity	Rate			Cost	Total
			Rs.	a.	p.	Rs.	
Bund R. L. 56·00.							
(1) Earthwork to bund with watering and tamping with lift and lead ...	...	8,276					
(2) Removing loose earth in breech ...	Lump sum						
(3) Trenching and excavation for puddle wall	Lump sum						
(4) Puddle wall	C.yds.	192					
(5) Removing and resetting old stone revetment	...	737					
(6) New stone revetment	...	1,303					
(7) Turfing	Sqr.	6,765					
(8) Grade stones figuring, painting, etc., complete	No.	25					
(9) Index stones	,,	25					
(10) Register number stone with survey and constructive details	,,	1					
(11) B. M. stones	,,	2					
(12) Gauge stone	,,	1					
(13) Jungle clearing and removing ant-hills	Grade	15					
(14) Cutting trenches and grips to old bund ...	,,	18					
Total Bund ...	...	...					
Sluice R. L. 45·00 No. 2 Sluice.							
(1) Excavation and refilling with consolidation	C.yds.	54					
(2) Concrete in surki mortar	C.ft.	214					
(3) Burnt brick in surki mortar	,,	640					
(4) Burnt stone slabs 4" to 6" thick dressed ...	S.ft.	189					
(5) Plastering with surki mortar	Sqr.	8·14					
(6) Providing plug and rod with locking arrangements	Lump sum						
Total Sluice 2 ...	...	...					
As per Sluice No. 2 for Sluice No. 1 ...	...	...					
Weir R. L. 50·00.							
(1) Earthwork excavation and using the earth to bund with watering and consolidation	C.yds.	586					
(2) Concrete in surki mortar	C.ft.	291					
(3) Burnt brick in surki mortar	,,	292					
(4) Plastering with surki mortar	Sqr.	5·36					
(5) Removing and resetting old stones work ...	C.yds.	45					
(6) New stone work	,,	150					
(7) Burnt stone slabs 4" to 6" thick ...	S.ft.	404					
(8) Providing jaggle joints	No.	12					
Total rupees ...	...	...					
Contingencies at 5% ...	...	...					
Grand Total rupees ...	...	...					

FORM OF ADVERTISEMENT.

Dated 31st March 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 22nd April 1929, for Restoring Yellampalli Sadliganakunte Minor Tank, R. No. 521 Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees Three hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Yellampalli Sadliganakunte, Bagepalli Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who dose not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executad at certain percentage is excess or lower than the estimate will not be accepted.

Abstract estimate for Restoring Yellampalli Sadliganakunte, Minor Tank Register No. 521, Bagepalli Taluk.

No.	Items of work	Quantity	Per	Rate	Cost	Total
	BUND AT R. L 56·00.			Rs.		
1	Earthwork to bund watering and tamping including lead and lift.	7,392	C.yd.			
2	Turfing	423	Sqrs.			
3	Removing and resetting old revetment with jelly backing.	285	C.yd.			
4	New stone work with jelly backing	1,195	,,			
5	Grade stones	15	No.			
6	Index stones	15	,,			
7	Register No. and survey constructive detail.	1	,,			
8	B. M. stones	2	,,			
9	Gauge stones	1	,,			
10	Jungle clearing	15	Grade			
	Total Bund					

No.	Items of work	Quantity	Per	Rate	Cost	Total
	SLUICE NO. 1 LEFT SIDE AT R. L. 44·50.			Rs.		
1	Earthwork	40	C.yds.			
2	Concrete in surki mortar	122	C.ft.			
3	Brick in surki mortar	316	,,			
4	Plastering with surki mortar ...	2·77	Sqrs.			
5	Burnt stone slabs 4" to 6" thick ...	132	S.ft.			
6	Cutting holes for vents, etc. ...	4	No.			
7	Cast iron pipes 5" diam of 9' each ..	36	R.ft.			
8	Providing plug and rod with locking arrangement.	1	L. S.			
	Total for sluice No. 1 ...	...	...	...	...	
	SLUICE NO. 2 RIGHT SIDE AT R. L 45·50. AS PER ABOVE SLUICE NO. 1.					
	Total for both sluices ...	...	...	...	...	
	WASTE WEIR.					
1	Earthwork	248	C.yd.			
2	Turfing	113	S.yds.			
3	Burnt stone slabs (6" thick) ..	558	S.ft.			
4	New stone work	63	C.yd.			
5	Resettting old stone with new je lly ...	Lump sum				
6	Patch repairs to existing body wall ...	Lump sum				
	Total weir ...	...	...	...	...	
	Total of bund, 2 sluices and waste weir.	...	..	...	...	
	Contingencies at 5 per cent ...	...	...	...	...	
	Grand Total Rupees ...	...	...	...	...	

FORM OF ADVERTISEMENT.

Dated 31*st March* 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 22nd April 1929, for restoring Devapalli Potiganakere Minor Tank Reg. No. 267 of Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees three hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Devapalli Potiganakere, Chintamani Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate of the cost of restoring Devapalli Potiganakere, Chintamani Taluk.

No.	Items of work	Per	Quantity	Rate	Cost	Total
	BUND.			Rs. a.p.	Rs.	
1	Earthwork watering and tamping with lift and lead.	C.yd.	3,520			
2	Gravel backing	„	82			
3	Turfing	Sqr.	25·86			
4	Resetting old stone with new jelly ...	C.yd.	210			
5	New stone work	„	637			
6	Stone pitching	„	76			
7	Fixing new grade stone with figuring painting etc., complete.	No.	14			
8	Do index stones do ...	„	14			
9	Do R. N. stone do ...	„	1			
10	Do B. M. stones do ...	„	2			
11	Do gauge stone do ...	„	1			
12	Do Cutting trees and removing ant hills.	Lump sum				
	Total bund ...	...	...			
	SLUICE No. 1.					
1	Earthwork excavation	C.yd.	143			
2	Refilling with watering and tamping ...	„	118			
3	Surki concrete	C.ft.	259			
4	Burnt brick in surki mortar	„	512			
5	Burnt stone slabs 6" thick dressed	S.ft.	237			
6	Surki mortar plastering	Sqr.	5·97			
7	Providing plug and rod with locking arrangements. Rs.	Lump sum				
8	Drilling holes in orifice and cross slabs Rs. ...	Lump sum				
9	Blocking up the present sluice Rs. ...	Lump sum				
	Total sluice No. 1 Rs. ...	...	...			
	Sluice No. 2 ...	...	...			
	As per Sluice No. 1 ... ... Rs....	...	...			
	WASTE WEIR.					
1	Earthwork excavation	C.yds.	335			
2	Surki concrete	C.ft.	681			
3	Burnt brick in surki mortar	„	2,897			
4	Burnt stone slabs 6" thick dressed ...	S.ft.	362			
5	Surki plastering	Sqr.	28·96			
6	Old stone work	C.yds.	33			
7	New Do	„	384			
8	Filling up bouldars below apron ... Rs	Lump sum				
9	Tangue and grave joints	No.	37			
	Total waste weir ...	...	...			
	Contingencies	Lump sum				
	Grand total Rs. ...	...	...	...	...	

N. LAKSHMINARASIMHAIYA,
Executive Engineer.